

MATERIAL LIST

C0824A Garage Plan

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	89.5"	16"	36	EA
2	MAIN EXT STUDS		2X6	14'	16"	36	EA
3	MAIN TREATED SILL		2X6			93	LF
4	MAIN INT PLATES		2X4			188	LF
5	MAIN EXT PLATES		2X6			279	LF
6	MAIN INT STUDS		2X4		16"	48	EA
7	MAIN FLOOR PLYWOOD		1 1/8"			456	SF
8	UPPER EXT STUDS		2X6	55.1"	16"	55	EA
9	UPPER EXT WALL PLATES		2X6			258	LF
10	UPPER INT PLATES		2X4			104	LF
11	UPPER INT WALL STUDS		2X4	VARIES	16"	26	EA
12	SHEET ROCK (Both Floors)					3523	SF
13	HEADER, (Ext Main Door)		4X8	4'		1	EA
14	HEADER, (Main Window)		4X8	5'		2	EA
15	HEADER, (Main Window)		4X10	6'		1	EA
16	HEADER, (Upper Window)		4X10	6'		2	EA
17	HEADER, (Ext Upper Door)		4X8	4'		4	EA
18	RAFTERS	B07	2X12	17'	24"	21	EA
19	EAVE BLOCKING		2X	22.5"	24"	19	EA
20	H2.5 RAFTER TIE				24"	21	EA
21	ROOF SHEATH		1/2" CDX			792	SF
22	ROOF FELT		30# Felt			792	SF
23	ROOFING					792	SF
24	BARGE RAFTERS		2X6	17'		4	EA
25	EXT WALL SHEATH		1/2" CDX			1034	SF
26	EXT WALL VAPOR		15# Felt			1034	SF
27	EXT SIDING (See Plan)		VARIES			1034	SF
28	STONE VENEER					225	SF
29	CONCRETE					9.01	CY
30	JOISTS	B06	2X8	12'	16"	15	EA
31	RIM JOIST					86	LF
32	UPPER FLOOR PLYWOOD		5/8"			456	SF
33	RIDGE BEAM	B03	2X14 DF#1	12'		1	EA
34	RIDGE BEAM	B04	2X14 DF#1	8'		4	EA
35	VALLEY RAFTERS	B01	1-3/4 X 14 LVL	20'		2	EA
36	BEAM	B05	5-1/8X9 GLB	8'		1	EA
37	BEAM		4X6	6'		11	EA
38	BEAM		4X6	8'		5	EA

39	BEAM		4X6	4'		5	EA
40	PORCH BEAM	P01	P.T. 4X10	10'		2	EA
41	PORCH BEAM	P02	P.T. 4X10	4'		1	EA
42	PORCH BEAM		P.T. 4X8	24'		1	EA
43	POST		P.T. 4X6	10'		4	EA
44	POST		2x4	120'		120	LF
45	PORCH CEILING		1/2 CDX			120	SF
46	PORCH RAILING		P.T. 2X6			34	LF
47	PORCH PICKETS		P.T. 2X2			84	EA
48	UPPER RAILING		VARIES			19	LF
49	POST (Crawl Space)		4X4 OR 4X6			42	LF
50	ANCHOR BOLTS		1/2"		48"	21	EA
51	POST BASE		BC46			4	EA
52	BASE CAPS		BC46			4	EA
53	STRAPS		LSTA18			12	EA
54	HANGERS		LUS26			46	EA
55	DECKING		VARIES			120	SF
56	POST		2x6	100'		120	LF
57	STAIR STRINGERS		2X12	16'		3	EA
58	STAIR TREADS					13	EA
59	STAIR RISERS					14	EA
60	STAIR PLATFORM					1	EA
61	POST GUSSETS					14	EA
62	PORCH LEDGER		P.T. 2X6			24	LF
63	PORCH JOISTS		P.T. 2X6	5'		18	EA