

MATERIAL LIST

C0280A Cabin Plan

Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	89.50	16"	48	EA
2	MAIN TREATED SILL		2X4			65	LF
3	MAIN INT PLATES		2X4			75	LF
4	MAIN EXT PLATES		2X6			204	LF
5	MAIN INT STUDS		2X4		16"	20	EA
6	MAIN FLOOR PLYWOOD		3/4"			280	SF
7	UPPER INT PLATES		2X4			16	LF
8	UPPER INT WALL STUDS		2X4	36"	16"	12	EA
9	UPPER SHEET ROCK (Optional)		1/2" GYP.			320	SF
10	HEADER, (Ext Main Door)		4X8	4'		1	EA
11	HEADER, (Main Window)		4X8	4'		4	EA
12	RAFTERS	B02	2X6	12'	16"	32	EA
13	EAVE BLOCKING		2X	14.0"	16"	30	EA
14	H2.5 RAFTER TIE				16"	32	EA
15	ROOF SHEATH		1/2" CDX			600	SF
16	ROOF FELT		30# Felt			600	SF
17	ROOFING					600	SF
18	BARGE RAFTERS		2X6	12'		4	EA
19	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			520	SF
20	MAIN INT WALL S.R. (Optional)		1/2" GYP.			400	SF
21	MAIN CEILING S.R. (Optional)		1/2" GYP.			280	SF
22	EXT WALL SHEATH		1/2" CDX			690	SF
23	EXT WALL VAPOR		15# Felt			690	SF
24	EXT SIDING (See Plan)		Varies			690	SF
25	CONCRETE					6.57	CY
26	UPPER/ LOWER JOISTS		2X6	14'	16"	22	EA
27	RIM JOIST					68	LF
28	UPPER FLOOR PLYWOOD		3/4"			280	SF
29	PORCH RAFTERS		2X6	14'		16	EA
30	PORCH PONY WALL STUDS		2X4	36"		16	EA
31	PORCH PONY WALL PLATE		2X4	20'		1	EA
32	PORCH JOISTS		PT 2X6	6'		32	EA
33	PORCH POSTS		PT 4X6	10'		3	EA
34	PORCH BEAM		PT 4X8	10'		4	EA
35	PORCH DECKING		PT 2X6			120	SF
36	RIDGE BEAM		2X12	20'		1	EA
37	ANCHOR BOLTS		1/2"		48"	17	EA