

MATERIAL LIST

Standard Foundation W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1		2X6	92-5/8"	16"	57	EA
2		2X6			80	LF
3		2X4			60	LF
4		2X6			160	LF
5		2X4		16"	24	EA
6		3/4"			384	SF
7		2x4	VARIES	16"	37	EA
8		1/2" GYP.			543	SF
9	N/A	4X12	6'		1	EA
10	N/A	4X8	4'		1	EA
11	N/A	4X8	4'		1	EA
12	N/A	4X8	5'		1	EA
13	B02	2x12	15'	16"	38	EA
14		2X	14.5"	16"	36	EA
15				16"	38	EA
16		1/2" CDX			815	SF
17		30# Felt			815	SF
18					662	SF
19		2X6	15'		4	EA
20		1/2" GYP.			616	SF
21		1/2" GYP.			480	SF
22		1/2" GYP.			384	SF
23		1/2" CDX			616	SF
24		15# Felt			616	SF
25		Varies			616	SF
26					4.24	CY
27	B01	2X6	16'	16"	9	EA
28		5/8"			140	SF
29		4X6	8'		4	EA
30	B02	2X6	16'		18	EA
31		4X4	6'		2	EA
32	B05	4X8	9'		2	EA
33		4X8	24'		1	EA
34	B04	4X8 P.T.	6'		2	EA
35		2X6 P.T.	6'		14	EA
36		2X6 P.T.	18'		13	EA
37		2X6	80'		80	LF
38		2X14	30'		1	EA
39		1/2"		48"	20	EA
40		5/8"			3	EA
41		HD5A W/ SSTB20			2	EA
42		HD2A			2	EA
43		LSTA18			10	EA
44		1- 1/8			384	SF

MATERIAL LIST

C0384A Cabin Plan

Pier Foundation W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	92-5/8"	16"	57	EA
2	MAIN TREATED SILL		2X6			80	LF
3	MAIN INT PLATES		2X4			60	LF
4	MAIN EXT PLATES		2X6			160	LF
5	MAIN INT STUDS		2X4		16"	24	EA
6	MAIN FLOOR PLYWOOD		1-1/8" T&G			384	SF
7	UPPER INT WALL STUDS		2x4	VARIABLES	16"	37	EA
8	UPPER CEILING S.R.		1/2" GYP.			543	SF
9	HEADER, (Main Window)	N/A	4X12	6'		1	EA
10	HEADER, (Ext Main Door)	N/A	4X8	4'		1	EA
11	HEADER, (Main Window)	N/A	4X8	4'		1	EA
12	HEADER, (Main Window)	N/A	4X8	5'		1	EA
13	RAFTERS	B02	2x12	15'	16"	38	EA
14	EAVE BLOCKING		2X	14.5"	16"	36	EA
15	H2.5 RAFTER TIE				16"	38	EA
16	ROOF SHEATH		1/2" CDX			815	SF
17	ROOF FELT		30# Felt			815	SF
18	ROOFING					662	SF
19	BARGE RAFTERS		2X6	15'		4	EA
20	MAIN EXT WALL S.R.		1/2" GYP.			616	SF
21	MAIN INT WALL S.R.		1/2" GYP.			480	SF
22	MAIN CEILING S.R.		1/2" GYP.			384	SF
23	EXT WALL SHEATH		1/2" CDX			616	SF
24	EXT WALL VAPOR		15# Felt			616	SF
25	EXT SIDING (See Plan)		Varies			616	SF
26	CONCRETE					3.27	CY
27	UPPER JOISTS	B01	2X6	16'	16"	9	EA
28	UPPER FLOOR PLYWOOD		5/8"			140	SF
29	POST		4X6	8'		4	EA
30	POST		4X4	6'		2	EA
31	DECK BEAM	B05	4X8	9'		2	EA
32	PORCH BEAM	B04	4X8 P.T.	6'		2	EA
33	DECK JOISTS		2X6 P.T.	6'		14	EA
34	DECKING		2X6 P.T.	18'		13	EA
35	RIDGE BEAM		2X14	30'		1	EA
36	STRAPS		LSTA18			10	EA
37	MAIN FLOOR BEAM		4X8			188	LF
38	HOLD DOWNS		HPAHD22			16	EA
39	FLOOR PLYWOOD		1- 1/8			384	SF