

MATERIAL LIST

C0384B Cabin Plan

Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
	MAIN EXT STUDS		2X6	89.50	16"	53	EA
1	MAIN TREATED SILL		2X6			71	LF
2	MAIN INT PLATES		2X4			72	LF
3	MAIN EXT PLATES		2X6			240	LF
4	MAIN INT STUDS		2X4		16"	20	EA
5	MAIN FLOOR PLYWOOD					384	SF
6	HEADER, (Ext Main Door)	N/A	4X10	4'		2	EA
7	HEADER, (Main Window)	N/A	4X10	4'		2	EA
8	HEADER, (Main Window)	N/A	4X10	5'		1	EA
9	HEADER, (Main Window)	N/A	4X6	4'		2	EA
10	RAFTERS	B02	2X12	16'	24"	13	EA
11	RAFTERS	B02	2X12	12'	24"	13	EA
12	EAVE BLOCKING		2X	22.0"	24"	24	EA
13	H2.5 RAFTER TIE				24"	78	EA
14	ROOF SHEATH		1/2" CDX			884	SF
15	ROOF FELT		30# Felt			884	SF
16	ROOFING					884	SF
17	BARGE RAFTERS		2X6			70	LF
18	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			568	SF
19	MAIN INT WALL S.R. (Optional)		1/2" GYP.			384	SF
20	MAIN CEILING S.R. (Optional)		1/2" GYP.			384	SF
21	EXT WALL SHEATH		1/2" CDX			568	SF
22	EXT WALL VAPOR		15# Felt			568	SF
23	EXT SIDING (See Plan)		Varies			568	SF
24	CONCRETE					3.70	CY
25	JOISTS	B05	2X8	16'	24"	13	EA
26	UPPER FLOOR PLYWOOD		3/4"			384	SF
27	PORCH RAFTERS	B06	2X8	16'		13	EA
28	PORCH ROOF BEAM	B08	4X8	8'		3	EA
29	DECK JOISTS	B09	2X6	8'		19	EA
30	DECK BEAM	B07	4X8	8'		3	EA
31	FLOOR BEAM	B04	4X6			140	LF
32	FLOOR BEAM	B10	4X10	12'		1	EA
33	DECKING		2X6			192	SF
34	RIDGE BEAM		2X12			24	LF
35	ANCHOR STRAPS		HPAHD22		48"	29	EA
36	STUDS		2X4	48"	16"	12	EA
37	PLATE		2X4			72	LF

MATERIAL LIST

C0384B Cabin Plan

Standard W/ Framed Roof and PIER Foundation

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
	MAIN EXT STUDS		2X6	91.13	16"	53	EA
1	MAIN TREATED SILL		2X6			71	LF
2	MAIN INT PLATES		2X4			72	LF
3	MAIN EXT PLATES		2X6			240	LF
4	MAIN INT STUDS		2X4		16"	20	EA
5	MAIN FLOOR PLYWOOD		3/4"			384	SF
6	HEADER, (Ext Main Door)	N/A	4X10	4'		2	EA
7	HEADER, (Main Window)	N/A	4X10	4'		2	EA
8	HEADER, (Main Window)	N/A	4X10	5'		1	EA
9	HEADER, (Main Window)	N/A	4X6	4'		2	EA
10	RAFTERS	B02	2X12	16'	24"	13	EA
11	RAFTERS	B02	2X12	12'	24"	13	EA
12	EAVE BLOCKING		2X	22.0"	24"	24	EA
13	H2.5 RAFTER TIE				24"	78	EA
14	ROOF SHEATH		1/2" CDX			884	SF
15	ROOF FELT		30# Felt			884	SF
16	ROOFING					884	SF
17	BARGE RAFTERS		2X6			70	LF
18	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			568	SF
19	MAIN INT WALL S.R. (Optional)		1/2" GYP.			384	SF
20	MAIN CEILING S.R. (Optional)		1/2" GYP.			384	SF
21	EXT WALL SHEATH		1/2" CDX			568	SF
22	EXT WALL VAPOR		15# Felt			568	SF
23	EXT SIDING (See Plan)		Varies			568	SF
24	CONCRETE					3.70	CY
25	JOISTS	B05	2X8	16'	24"	13	EA
26	UPPER FLOOR PLYWOOD		5/8"			136	SF
27	PORCH RAFTERS	B06	2X8	16'		13	EA
28	PORCH ROOF BEAM	B08	4X8	8'		3	EA
29	DECK JOISTS	B09	2X6	8'		19	EA
30	DECK BEAM	B07	4X8	8'		3	EA
31	FLOOR BEAM	B04	4X6			140	LF
32	FLOOR BEAM	B10	4X10	12'		1	EA
33	DECKING		2X6			192	SF
34	RIDGE BEAM		2X12			24	LF
35	ANCHOR STRAPS		HPAHD22		48"	29	EA
36	STUDS		2X4	48"	16"	12	EA
37	PLATE		2X4			72	LF