

MATERIAL LIST

C0496A Cabin Plan
Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	89.5" (Varies)	16"	64	EA
2	MAIN TREATED SILL		2X6			92	LF
3	MAIN EXT PLATES		2X6			276	LF
4	MAIN INT STUDS		2X4		16"	27	EA
5	MAIN INT PLATES		2X4			102	LF
6	HEADER, (Ext Main Door)		4X8	4'		2	EA
7	HEADER, (Main Window)		4X8	3'		2	EA
8	HEADER, (Main Window)		4X8	5'		4	EA
9	HEADER, (Main Window)		4X10	8'		2	EA
10	HEADER, (Main Window)		4X8	2		2	EA
11	TRUSSES			24' + OH	24"	9	EA
12	TRUSSES (Ends)					2	EA
13	EAVE BLOCKING		2X	24"	24"	24	EA
14	H2.5 RAFTER TIE				24"	26	EA
15	ROOF SHEATH		1/2 CDX			834	SF
16	ROOF FELT		30# Felt			834	SF
17	ROOFING		Composition			834	SF
18	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			688	SF
19	MAIN INT WALL S.R. (Optional)		1/2" GYP.			544	SF
20	MAIN CEILING S.R. (Optional)		1/2" GYP.			528	SF
21	WALL SHEATH		1/2" CDX			769	SF
22	WALL VAPOR		15# Felt			769	SF
23	SIDING (See Plan)					769	SF
24	CONCRETE					7.52	CY
25	JOISTS	B16	2X10	22'	24"	13	EA
26	PORCH JOISTS		2X6	8'		12	EA
27	PORCH DECKING		2X6			176	SF
28	FLOOR BLCKING	B14,B15	2X10	88'		1	EA
29	BEAM (Porch Rafters)	C02	2X8	14'		12	EA
30	BEAM (Porch Post)		6X6	8'		3	EA
31	BEAM (Porch Beam)	C01	6X12	10'		2	EA
32	BARGE RAFTERS		2X6	18'		4	EA
33	HOLD DOWNS		HPAHD22			26	EA
34	FLOOR PLY		1-1/8" T&G PLY			528	SF

MATERIAL LIST

C0496A Cabin Plan Pier Vers.
Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	89.5" (Varies)	16"	64	EA
2	MAIN TREATED SILL		2X6			92	LF
3	MAIN EXT PLATES		2X6			276	LF
4	MAIN INT STUDS		2X4		16"	27	EA
5	MAIN INT PLATES		2X4			102	LF
6	HEADER, (Ext Main Door)		4X8	4'		2	EA
7	HEADER, (Main Window)		4X8	3'		2	EA
8	HEADER, (Main Window)		4X8	5'		4	EA
9	HEADER, (Main Window)		4X10	8'		2	EA
10	HEADER, (Main Window)		4X8	2		2	EA
11	TRUSSES			24' + OH	24"	9	EA
12	TRUSSES (Ends)					2	EA
13	EAVE BLOCKING		2X	24"	24"	24	EA
14	H2.5 RAFTER TIE				24"	26	EA
15	ROOF SHEATH		1/2 CDX			834	SF
16	ROOF FELT		30# Felt			834	SF
17	ROOFING		Composition			834	SF
18	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			688	SF
19	MAIN INT WALL S.R. (Optional)		1/2" GYP.			544	SF
20	MAIN CEILING S.R. (Optional)		1/2" GYP.			528	SF
21	WALL SHEATH		1/2" CDX			769	SF
22	WALL VAPOR		15# Felt			769	SF
23	SIDING (See Plan)					769	SF
24	CONCRETE					7.52	CY
25	JOISTS	B16	2X10	22'	24"	13	EA
26	PORCH JOISTS		2X6	8'		12	EA
27	PORCH DECKING		2X6			176	SF
28	FLOOR BLCKING	B14,B15	2X10	88'		1	EA
29	BEAM (Porch Rafters)	C02	2X8	14'		12	EA
30	BEAM (Porch Post)		6X6	8'		3	EA
31	BEAM (Porch Beam)	C01	6X12	10'		2	EA
32	BARGE RAFTERS		2X6	18'		4	EA
33	HOLD DOWNS		HPAHD22			26	EA
34	FLOOR PLY		1-1/8" T&G PLY			528	SF