

MATERIAL LIST

C0618A Cabin Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	89.50	16"	73	EA
2	MAIN TREATED SILL		2X6			98	LF
3	MAIN INT PLATES		2X4			201	LF
4	MAIN EXT PLATES		2X6			318	LF
5	MAIN INT STUDS		2X4	VARIES 8'-13'	16"	52	EA
6	MAIN FLOOR PLYWOOD		1 1/8"			682	SF
7	HEADER, (Ext Main Door)		4X8	4'		1	EA
8	HEADER, (Ext Main Door)		4X10	6'		1	EA
9	HEADER, (Main Window)		4X8	3'		2	EA
10	HEADER, (Main Window)		4X10	6'		4	EA
11	HEADER, (Main Window)		4X10	7'		1	EA
12	TRUSSES				24"	15	EA
13	TRUSSES					2	EA
14	EAVE BLOCKING		2X	22.5"	24"	34	EA
15	H2.5 RAFTER TIE				24"	34	EA
16	ROOF SHEATH		1/2" CDX			1074	SF
17	ROOF FELT		30# Felt			1074	SF
18	ROOFING					1074	SF
19	BARGE RAFTERS		2X6	12'		4	EA
20	BARGE RAFTERS		2X6	17'		4	EA
21	GYPSUM BOARD		1/2"			2538	SF
22	EXT WALL SHEATH		1/2" CDX			784	SF
23	EXT WALL VAPOR		15# Felt			784	SF
24	EXT SIDING (See Plan)		Varies			784	SF
25	CONCRETE					8.15	CY
26	GIRDER TRUSS			15'		1	EA
27	FLOOR BEAM		4X6			274	LF
28	POST		4X4			36	LF
29	CEILING JOIST (OVER BATH)		2X6	12'		12	EA
30	ANCHOR BOLTS		1/2"		48"	25	EA
31	HOLD DOWNS		HD2A W/SSTB16			2	EA