

MATERIAL LIST**C0768J Cabin Plan**

Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	EXTERIOR STUDS		2X6	89.5"		66	EA
2	EXTERIOR STUDS		2X6	108"		18	EA
3	EXTERIOR STUDS		2X6			120	LF
4	EXTERIOR STUDS		2X6	3'		20	EA
5	EXTERIOR PLATES		2X6 PT			112	LF
6	EXTERIOR PLATES		2X6			336	LF
7	EXTERIOR PLATES		2X6			72	LF
8	UPPER EXTERIOR PLATES		2X6			72	LF
9	UPPER INTERIOR STUDS		2X4	6'		20	EA
10	INTERIOR STUDS		2X4	89.5"		83.6	EA
11	INTERIOR PLATES		2X4			72	LF
12	INTERIOR PLATES		2X4			250	LF
13	RAFTERS		2X12	14.5'		18	EA
14	RAFTERS	B04	2X12	16.5'		18	EA
15	RAFTERS		2X12	18'		18	EA
16	UPPER FLOOR JOISTS	B05	2X8	18'		18	EA
17	UPPER FLOOR RIM		2X8			32	LF
18	MAIN FLOOR RIM JOISTS		2X8			64	LF
19	MAIN FLOOR POST		4X4	VARIABLE		VARIABLE	LF
20	MAIN FLOOR PLYWOOD		3/4"			768	SF
21	UPPER FLOOR PLYWOOD		3/4"			432	SF
22	CEILING S.R.		1/2" GYP.			1008	SF
23	UPPER EXT WALL S.R.		1/2" GYP.			264	SF
24	MAIN WALL S.R.		1/2" GYP.			2291	SF
25	HEADER, (Upper Window)		4X8	4'		5	EA
26	HEADER, (Main Window)		4X8	5'		2	EA
27	HEADER, (Main Window)		4X8	4'		5	EA
28	HEADER, (Ext Main Door)		4X8	4'		1	EA
29	HEADER, (Ext Main Door)		4X10	6'		2	EA
30	H2.5 RAFTER TIE				12"	54	EA
31	ROOF SHEATH		1/2" CDX			1000	SF
32	ROOF FELT		30# Felt			1000	SF
33	ROOFING					1000	SF
34	BARGE RAFTERS		2X6	15'		4	EA
35	EXT WALL SHEATH		1/2" CDX			1328	SF
36	EXT WALL VAPOR		15# Felt			1328	SF
37	EXT SIDING (See Plan)		Varies			1078	SF
38	EXT SIDING FIREPLACE (See Plan)					250	SF

39	CONCRETE					10.20	CY
40	FLOOR BEAM	B02	4X10	32'		1	EA
41	MAIN FLOOR JOISTS	B01	2X8	12'		48	EA
42	CEILING BEAM	B03	5-1/8X19-1/2 GLB	24'		1	EA
43	ANCHOR BOLTS		1/2"		48"	25	EA
44	HOLD DOWNS		HD3B W/SSTB16			8	EA
45	DECK JOISTS		2X6 P.T.	8'		24	EA
46	DECKING		2X6 P.T.			384	SF
47	RAILING		2X6 P.T.			80	LF
48	PICKETS		2X2 P.T.	3'		214	EA
49	POSTS		4X4 P.T.	VARIES		8.00	EA
50	RIM JOISTS		2X6 P.T.			48	LF
51	LEDGER		2X6 P.T.			48	LF
52	INSULATION		R38			528	SF
53	INSULATION		R21			1328	SF
54	INSULATION		R25			768	SF