

MATERIAL LIST

C1277A Cabin Plan

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS	2X6	91.50	16"	82	EA
2	MAIN TREATED SILL	2X6			110	LF
3	MAIN EXT PLATES	2X6			348	LF
4	MAIN INT STUDS	2X4		16"	51	EA
5	MAIN INT PLATES	2X4			198	LF
6	UPPER INT WALL STUDS	2X4	5'	24"	33	EA
7	UPPER INT PLATES	2X4			192	LF
8	HEADER, (Ext Main Door)	4X8	4'		2	EA
9	HEADER, (Main Window)	4X8	4'		3	EA
10	HEADER, (Main Window)	4X8	4'		3	EA
11	HEADER, (Main Window)	4X8	3'		1	EA
12	HEADER, (Upper Window)	3-1/8X9 GLB	5		2	EA
13	HEADER, (Upper Window)	4X12	4		2	EA
14	RAFTERS	2X10	18'	24"	38	EA
15	EAVE BLOCKING	2X	22.5	24"	36	EA
16	H2.5 RAFTER TIE			24"	38	EA
17	ROOF SHEATH	1/2 CDX			1490	SF
18	ROOF FELT	30# Felt			1490	SF
19	ROOFING	Composition			1490	SF
20	MAIN EXT WALL S.R. (Optional)	1/2" GYP.			880	SF
21	MAIN INT WALL S.R. (Optional)	1/2" GYP.			1056	SF
22	MAIN CEILING S.R. (Optional)	1/2" GYP.			792	SF
23	WALL SHEATH	1/2" CDX			1122	SF
24	WALL VAPOR	15# Felt			1122	SF
25	SIDING (See Plan)				1122	SF
26	CONCRETE				15.43	CY
27	JOISTS	2X12	24'	16"	28	EA
28	RIM JOIST				120	LF
29	UPPER FLOOR PLYWOOD	5/8" PLY			792	SF
30	RIDGE BEAM	3-1/8x18 GLB	36'		1	EA
31	FLOOR BEAM	3-1/8X12 GLB	18'		1	EA
32	POSTS	4X4	67		1	EA
33	BEAM (P.T. Posts)	4X4	9		2	EA
34	BEAM (P.T. Porch Beam)	4X10	12		3	EA
35	BEAM (Porch Beam)	4X10	12		3	EA
36	UPPER S.R. (Optional)				936	SF
37	BARGE RAFTERS	2X6	20'		3	EA
38	ANCHOR BOLTS	1/2		48"	28	EA
39	HOLD DOWNS	HD2A W/SSTB16			4	EA
40	FLOOR PLY	1-1/8" T&G PLY			792	SF
41	4X6 (P.T. Posts)	4X6	9'		2	EA
42	PORCH RAFTERS	2X8	14'		27	EA
43	PORCH JOISTS	P.T. 2X6	6'		45	EA
44	PORCH LEDGER	P.T. 2X6			36	LF
45	PORCH DECKING				216	SF
46	4X6 (Posts)	4X6	9'		3	EA
47	BARGE RAFTERS	2X6	14'		2	EA
48	FLOOR POSTS	4X4	VARIES		30	EA
49	FLOOR BEAMS	4X6	180'		180'	LF