

MATERIAL LIST

C1284A Cabin Plan Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	103.1" (Varies)	16"	85	EA
2	MAIN TREATED SILL		2X6			114	LF
3	MAIN EXT PLATES		2X6			360	LF
4	MAIN INT STUDS		2X4		16"	51	EA
5	MAIN INT PLATES		2X4			198	LF
6	UPPER INT WALL STUDS		2X4	48"	16"	49	EA
7	UPPER INT PLATES		2X4			192	LF
8	HEADER, (Ext Main Door)	N/A	4X8	4'		2	EA
9	HEADER, (Main Window)	B08	4X8	4'		3	EA
10	HEADER, (Main Window)	B08	4X8	4'		3	EA
11	HEADER, (Main Window)	N/A	4X8	3'		1	EA
12	HEADER, (Upper Window)	B02, B03	3-1/8X9 GLB	5		2	EA
13	HEADER, (Upper Window)	N/A	4X8	4		2	EA
14	RAFTERS	B04	2X12	18'	24"	38	EA
15	EAVE BLOCKING		2X	22.5	24"	36	EA
16	H2.5 RAFTER TIE				24"	38	EA
17	ROOF SHEATH		1/2 CDX			1597	SF
18	ROOF FELT		30# Felt			1597	SF
19	ROOFING		Composition			1597	SF
20	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			1026	SF
21	MAIN INT WALL S.R. (Optional)		1/2" GYP.			1188	SF
22	MAIN CEILING S.R. (Optional)		1/2" GYP.			864	SF
23	WALL SHEATH		1/2" CDX			1314	SF
24	WALL VAPOR		15# Felt			1314	SF
25	SIDING (See Plan)					1314	SF
26	CONCRETE					15.70	CY
27	JOISTS	B06	2X12	24'	16"	28	EA
28	RIM JOIST					120	LF
29	UPPER FLOOR PLYWOOD		5/8" PLY			864	SF
30	RIDGE BEAM	B01, B01E	5-1/8x16-1/2 GLB	36'		1	EA
31	FLOOR BEAM	B07, B07E	3-1/8X12 GLB	23'		1	EA
32	POSTS	N/A	4X4	67'		67	LF
33	BEAM (P.T. Posts)	N/A	4X4	9		2	EA
34	BEAM (P.T. Porch Beam)	B10	4X10	12		3	EA
35	BEAM (Porch Beam)	B11	4X10	12		3	EA
36	UPPER S.R. (Optional)					936	SF
37	BARGE RAFTERS		2X6	20'		3	EA
38	ANCHOR BOLTS		1/2		48"	29	EA
39	HOLD DOWNS		HD2A W/SSTB16			4	EA
40	FLOOR PLY		1-1/8" T&G PLY			864	SF
41	4X6 (P.T. Posts)		4X6	9'		2	EA
42	PORCH RAFTERS	B05	2X8	14'		27	EA
43	PORCH JOISTS		P.T. 2X6	6'		45	EA
44	PORCH LEDGER		P.T. 2X6			36	LF
45	PORCH DECKING					216	SF
46	4X6 (Posts)		4X6	9'		3	EA
47	BARGE RAFTERS		2X6	14'		2	EA
48	FLOOR POSTS		4X4	VARIES		30	EA
49	FLOOR BEAMS		4X6	180'		180'	LF