MATERIAL LIST

C1340A Cabin Plan

Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	91.5" (Varies)	16"	85	EA
1	MAIN TREATED SILL		2X6			114	LF
2	MAIN EXT PLATES		2X6			342	LF
3	MAIN INT STUDS		2X4		16"	41	EA
4	MAIN INT PLATES		2X4			156	LF
5	UPPER EXT WALL PLATES		2X4			120	LF
6	UPPER INT WALL STUDS (Inc. Rail)		2X4	5'	16"	55	EA
7	UPPER INT PLATES (Inc. Rail)		2X4	5'		216	LF
8	HEADER, (Ext Main Door)		4X8	4'		1	EA
9	HEADER, (Ext Main Door)		4X10	5'		1	EA
10	HEADER, (Main Window)		4X8	5'		6	EA
11	HEADER, (Ext Main Door)	B09	5-1/8 X 9 GLB	7'		1	EA
12	HEADER, (Upper Window)		4X8	4'		4	EA
13	HEADER, (Main Window)		4X8	4'		2	EA
14	HEADER, (Main Window)		4X10	7'		1	EA
15	RAFTERS	B02	2X12	20'	24"	42	EA
16	EAVE BLOCKING		2X	22.5	24"	40	EA
17	H2.5 RAFTER TIE				24"	42	EA
18	ROOF SHEATH		1/2 CDX			1544	SF
19	ROOF FELT		30# Felt			1544	SF
20	ROOFING		Composition			1544	SF
21	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			912	SF
22	MAIN INT WALL S.R. (Optional)		1/2" GYP.			832	SF
23	MAIN CEILING S.R. (Optional)		1/2" GYP.			960	SF
24	WALL SHEATH		1/2" CDX			1200	SF
25	WALL VAPOR		15# Felt			1200	SF
26	SIDING (See Plan)					1200	SF
27	CONCRETE					10.05	CY
28	JOISTS	B03	2X12	24'	16"	28	EA
29	RIM JOIST					128	LF
30	UPPER FLOOR PLYWOOD		5/8" PLY			720	SF
31	RIDGE BEAM	B01	5-1/8x18 GLB	40'		1	EA
32	Floor Beam (Crawl Space)		4X6	40'		5	EA
33	FLOOR BEAM	B08	3-1/8X10-1/2 GLB	12'		1	EA
34	4X4 Posts		4X4	8'		4	EA
35	4X6 Posts		4X6	20'		1	EA
36	BEAM (Porch Beam)	B07	4X8	10'		4	EA
37	UPPER S.R. (Optional)		1/2" GYP.			1280	SF
38	BARGE RAFTERS		2X6	20'		2	EA
39	BARGE RAFTERS		2X6	10'		2	EA
40	BARGE RAFTERS		2X6	12'		2	EA
41	ANCHOR BOLTS		1/2		48"	29	EA
42	HOLD DOWNS		HD2A W/SSTB16			4	EA
43	PORCH ROOF BEAM	B04	4X8	10		4	EA
44	FLOOR PLY		1-1/8" PLYWOOD			960	SF
45	4X4 PST (Crawl Space)		4X4 POST	VARIES		24	EA
46	6X8 Posts		6X8	20'		1	EA
47	PORCH RAFTERS		2X6	14'		21	EA
48	FLOOR BEAM	B06	5-1/8X13-1/2 GLB	20'		1	EA
49	FLOOR BEAM		6-1/8X15 GLB	16'		1	EA