

**MATERIAL LIST**

**H1485A Garage Plan**

Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	VARIES	16"	95	EA
2	MAIN TREATED SILL		2X6			116	LF
3	MAIN EXT PLATES		2X6			475	LF
4	UPPER EXT STUDS		2X6	91.00	16"	97	EA
5	UPPER INT PLATES		2X4			180	EA
6	UPPER INT WALL STUDS		2X4	VARIES	16"	46	EA
7	UPPER CEILING		1/2" GYP.			586	SF
8	UPPER EXT WALL S.R. (Optional)		1/2" GYP.			1045	SF
9	UPPER INT WALL S.R. (Optional)		1/2" GYP.			960	SF
10	HEADER, (Ext Main Garage Door)	B01	3-1/8X12 GLB	10'		2	EA
11	HEADER, (Ext Main Door)	N/A	4X8	4'		1	EA
12	HEADER, (Ext Upper Door)	N/A	4X8	4'		2	EA
13	HEADER, (Upper Window)	N/A	4X8	6'		2	EA
14	HEADER, (Upper Window)	N/A	4X8	5'		3	EA
15	HEADER, (Upper Window)	N/A	4X8	3'		1	EA
16	HEADER, (Upper Window)	N/A	4X8	6'		1	EA
17	RAFTERS		2X12	27'	24"	38	EA
18	RAFTERS		2X12	14'	24"	20	EA
19	EAVE BLOCKING		2X	22.5"	24"	36	EA
20	H2.5 RAFTER TIE				24"	38	EA
21	ROOF SHEATH		1/2" CDX			2053	SF
22	ROOF FELT		30# Felt			2053	SF
23	ROOFING					2053	SF
24	BARGE RAFTERS		2X8	28'		4	EA
25	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			694	SF
26	MAIN CEILING S.R. (Optional)		1/2" GYP.			1163	SF
27	EXT WALL SHEATH		1/2" CDX			694	SF
28	EXT WALL VAPOR		15# Felt			694	SF
29	EXT SIDING (See Plan)		Varies			694	SF
30	CONCRETE					36.21	CY
31	JOISTS	B08	2X10	16'	16"	56	EA
32	RIM JOIST		2X10			137	LF
33	UPPER FLOOR PLYWOOD		5/8"			994	SF
34	RIDGE BEAM	B01	3-1/8X12 GLB	38'		2	EA
35	RIDGE BEAM	B01	3-1/8X12 GLB	41'		2	EA
36	RIDGE BEAM	B01	3-1/8X12 GLB	44'		1	EA
37	POST	N/A	4X4	13'		1	EA
38	POST	N/A	4X4	6'		1	EA

39	POST	N/A	4X4	8'		2	EA
40	POST	N/A	4X4	3'		2	EA
41	POST	N/A	3-1/8X12 GLB	23'		1	EA
42	POST	N/A	4X6	17'		2	EA
43	POST	N/A	4X6	12'		2	EA
44	POST	N/A	6X6	9'		2	EA
45	FLOOR BEAM	B05	5-1/8X12 GLB	16'		1	EA
46	FLOOR BEAM	B04	5-1/8X13-1/2 GLB	20'		1	EA
47	FLOOR BEAM	N/A	4X10	20'		3	EA
48	FLOOR BEAM	N/A	4X10	16'		2	EA
49	FLOOR BEAM	B10	5-1/8X13-1/2 GLB	17'		1	EA
50	FLOOR BEAM	B12	3-1/8X12 GLB	20'		1	EA
51	DECK BEAM	B11	6-3/4X12 GLB	22'		2	EA
52	DECK BEAM	N/A	2X12	11'		2	EA
53	DECK BEAM	N/A	2X12	11'		4	EA
54	DECK JOISTS	N/A	2X6	8'		28	EA
55	DECKING		2X6 P.T.			500 SF	EA
56	LOFT FLOOR		1-1/8" T&G PLYWD			586 SF	EA
57	ANCHOR BOLTS		1/2"		48"	29	EA
58	WIRE MESH		6X6 W1.4 X W1.4			994	SF