

**MATERIAL LIST**

**C0199A Cabin Plan**

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1 MAIN EXT STUDS		2X6	89.50	16"	47	EA
2 MAIN TREATED SILL		2X6			58	LF
3 MAIN INT PLATES		2X4			54	LF
4 MAIN EXT PLATES		2X6			174	LF
5 MAIN INT STUDS		2X4		16"	15	EA
6 MAIN FLOOR PLYWOOD		3/4"			204	SF
7 GYPSUM BOARD		1/2"			1080	SF
8 UPPER CEILING S.R. (Optional)		1/2" GYP.			340	SF
9 HEADER, (Ext Main Door)	N/A	4X8	4'		1	EA
10 HEADER, (Main Window)	N/A	4X8	4'		3	EA
11 HEADER, (Upper Window)	N/A	4X8	4'		2	EA
12 RAFTERS	B02	2X8	14'	16"	27	EA
13 EAVE BLOCKING		2X	14.5"	16"	25	EA
14 H2.5 RAFTER TIE				16"	27	EA
15 ROOF SHEATH		1/2" CDX			442	SF
16 ROOF FELT		30# Felt			442	SF
17 ROOFING					442	SF
18 BARGE RAFTERS		2X6	14'		4	EA
19 EXT WALL SHEATH		1/2" CDX			648	SF
20 EXT WALL VAPOR		15# Felt			648	SF
21 EXT SIDING (See Plan)		Varies			648	SF
22 CONCRETE					6.46	CY
23 JOISTS	B01	2X8	20'	16"	14	EA
24 UPPER FLOOR PLYWOOD		3/4"			204	SF
25 P.T. PORCH BEAM	B03	4X12	10'		2	EA
26 P.T. PORCH BEAM	B05	4X8	10'		2	EA
27 P.T. PORCH POST		4X6	10'		3	EA
28 P.T. DECKING		2X6	VARIES		77	SF
29 RIDGE BEAM		2X10	17'		1	EA
30 MAIN FLOOR BEAM		4X8	10'		2	EA
31 MAIN FLOOR JOISTS		2X6	12'		13	EA
32 ANCHOR BOLTS		1/2"		48"	16	EA
33 LSTA18 STEEL STRAPS					7	EA