

MATERIAL LIST**C0560A Cabin Plan**
Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	91.13	16"	69	EA
2	MAIN TREATED SILL		2X6			93	LF
3	MAIN INT PLATES		2X4			80	LF
4	MAIN EXT PLATES		2X6			192	LF
5	MAIN INT STUDS		2X4		16"	32	EA
6	UPPER INT PLATES		2X4			56	LF
7	UPPER INT WALL STUDS		2X4	VARIES	16"	43	EA
8	SHEETROCK		1/2" GYP.			2736	SF
9	HEADER, (Main Window)		4X12	9'		1	EA
10	HEADER, (Ext Main Door)		4X8	4'		1	EA
11	HEADER, (Main Window)		4X8	4'		1	EA
12	HEADER, (Upper Window Header)	B03	4X10	5'		1	EA
13	HEADER, (Main Window)		4X8	3'		1	EA
14	HEADER, (Window Header)		4X8	5'		1	EA
15	RAFTERS	B02	2x12	15'	24"	30	EA
16	EAVE BLOCKING		2X	22.5"	24"	28	EA
17	H2.5 RAFTER TIE				24"	30	EA
18	ROOF SHEATH		1/2" CDX			1250	SF
19	ROOF FELT		30# Felt			1250	SF
20	ROOFING					1250	SF
21	BARGE RAFTERS		2X6	15'		4	EA
22	EXT WALL SHEATH		1/2" CDX			1324	SF
23	EXT WALL VAPOR		15# Felt			1324	SF
24	EXT SIDING (See Plan)		Varies			1324	SF
25	CONCRETE					6.00	CY
26	MAIN FLOOR JOISTS		2X10	11'		13	EA
27	MAIN FLOOR JOISTS		2X10	9'		13	EA
28	MAIN FLOOR RIM		2X10			100	LF
29	UPPER JOISTS	B01	2X10	14.5'	16"	14	EA
30	UPPER FLOOR JOISTS CANT.	B01A	2X10	18'		4	EA
31	UPPER RIM JOIST		2X10			69	LF
32	MAIN FLOOR PLYWOOD		3/4"			560	SF
33	UPPER FLOOR PLYWOOD		3/4"			300	SF
34	POST		4X6	8'		3	EA
35	POST		6X6	10'		1	EA
36	POST		4X4	7'		2	EA
37	BEAM	B05 / B07	4X8	10'		6	EA
38	FLOOR BEAM	B06	4X10	7'		4	EA
39	RIDGE BEAM	B04	3-1/8 x 13-1/2	28'		1	EA
40	FIRESTOPS		2X6			69	LF
41	DECK JOISTS			6'		14	EA
42	DECKING			18'		13	EA
43	ANCHOR BOLTS		1/2"		48"	24	EA
44	HOLD DOWNS		HD5B W/ SSTB20			4	EA

MATERIAL LIST

C0560A Cabin Plan

Pier Version W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	91.13	16"	69	EA
2	MAIN TREATED SILL		2X6			93	LF
3	MAIN INT PLATES		2X4			80	LF
4	MAIN EXT PLATES		2X6			192	LF
5	MAIN INT STUDS		2X4		16"	32	EA
6	UPPER INT PLATES		2X4			56	LF
7	UPPER INT WALL STUDS		2X4	VARIES	16"	43	EA
8	SHEETROCK		1/2" GYP.			2736	SF
9	HEADER, (Main Window)		4X12	9'		1	EA
10	HEADER, (Ext Main Door)		4X8	4'		1	EA
11	HEADER, (Main Window)		4X8	4'		1	EA
12	HEADER, (Upper Window Header)	B03	4X10	5'		1	EA
13	HEADER, (Main Window)		4X8	3'		1	EA
14	HEADER, (Window Header)		4X8	5'		1	EA
15	RAFTERS	B02	2x12	15'	24"	30	EA
16	EAVE BLOCKING		2X	22.5"	24"	28	EA
17	H2.5 RAFTER TIE				24"	30	EA
18	ROOF SHEATH		1/2" CDX			1250	SF
19	ROOF FELT		30# Felt			1250	SF
20	ROOFING					1250	SF
21	BARGE RAFTERS		2X6	15'		4	EA
22	EXT WALL SHEATH		1/2" CDX			1324	SF
23	EXT WALL VAPOR		15# Felt			1324	SF
24	EXT SIDING (See Plan)		Varies			1324	SF
25	CONCRETE					3.00	CY
26	MAIN FLOOR JOISTS		2X10	11'		13	EA
27	MAIN FLOOR JOISTS		2X10	9'		13	EA
28	UPPER JOISTS	B01	2X10	14.5'	16"	14	EA
29	UPPER FLOOR JOISTS CANT.	B01A	2X10	18'		4	EA
30	UPPER RIM JOIST		2X10			69	LF
31	MAIN FLOOR PLYWOOD		3/4"			560	SF
32	UPPER FLOOR PLYWOOD		3/4"			300	SF
33	POST		4X6	8'		3	EA
34	POST		6X6	10'		1	EA
35	POST		4X4	7'		2	EA
36	BEAM		4X8	10'		4	EA
37	BEAM		4X8	6'		2	EA
38	BEAM	B14/ B16	3-1/8 x 10-1/2	20'		3	EA
39	BEAM	B14/ B16	3-1/8 x 10-1/2	10'		1	EA
40	BEAM	B15	3-1/8 x 10-1/2	16'		3	EA
41	BEAM	B15	3-1/8 x 10-1/2	12'		3	EA
42	RIDGE BEAM	B04	3-1/8 x 13-1/2	28'		1	EA
43	FIRESTOPS		2X6			69	LF

44	DECK JOISTS			6'		14	EA
45	DECKING			18'		13	EA
46	STRAPS		MSTC48B3			9	EA
47	HOLDDOWNS		HPAHD22			18	EA