

MATERIAL LIST

C0560B Cabin Plan

Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	89.50	16"	36	EA
2	MAIN EXT STUDS		2X6	10'-6"	16"	36	EA
3	MAIN INT PLATES		2X4			138	LF
4	MAIN EXT PLATES		2X6			192	LF
5	MAIN INT STUDS		2X4		16"	36	EA
6	MAIN FLOOR PLYWOOD		3/4"			560	SF
7	UPPER EXT STUDS		2X6	22.00	16"	36	EA
8	UPPER INT PLATES		2x4			34	LF
9	UPPER INT WALL STUDS		2x4	VARIES	16"	26	EA
10	UPPER CEILING S.R. (Optional)		1/2" GYP.			792	SF
11	UPPER EXT WALL S.R. (Optional)		1/2" GYP.			192	SF
12	HEADER, (Main Window)	N/A	4X12	11'		1	EA
13	HEADER, (Ext Main Door)	N/A	4X8	4'		2	EA
14	HEADER, (Main Window)	N/A	4X8	3'		1	EA
15	HEADER, (Main Window)	N/A	4X8	4'		1	EA
16	HEADER, (Main Window)	N/A	4X8	5'		1	EA
17	HEADER, (Upper Window)	B03	4X10	5'		2	EA
18	RAFTERS	B02	2x12	16'	24"	30	EA
19	EAVE BLOCKING		2X	22.5"	24"	28	EA
20	H2.5 RAFTER TIE				24"	30	EA
21	ROOF SHEATH		1/2" CDX			1008	SF
22	ROOF FELT		30# Felt			1008	SF
23	ROOFING					1008	SF
24	BARGE RAFTERS		2X6	16'		6	EA
25	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			720	SF
26	MAIN INT WALL S.R. (Optional)		1/2" GYP.			736	SF
27	MAIN CEILING S.R. (Optional)		1/2" GYP.			560	SF
28	EXT WALL SHEATH		1/2" CDX			720	SF
29	EXT WALL VAPOR		15# Felt			720	SF
30	EXT SIDING (See Plan)		Varies			720	SF
31	UPPER FLOOR JOISTS	B10	2X10	14'		13	EA
32	UPPER FLOOR JOISTS		2X10	18'		7	EA
33	UPPER FLOOR PLYWOOD		5/8"			240	SF
34	POST RIDGE SUPPORT		6X6	10'		2	EA
35	PORCH BEAM	B05	4X8	10'		3	EA
36	GABLE END STUDS		2X6	260'		260	LF
37	PORCH BEAM	B07	4X10	10'		3	EA
38	PORCH JOISTS		2X6	6'		21	EA
39	PORCH DECKING		2X6	12'		28	EA
40	PORCH RAFTERS		2X6	10'		21	EA
41	RIDGE BEAM	B01	3-1/8X13-1/2 GLB	14'		2	EA
42	PORCH CEILING JOISTS		2X6	6'		14	EA
43	STRAP		LSTA18			14	EA
44	CONCRETE					8.5	CY
45	FLOOR BEAM		4X8	7		5	EA
46	MAIN FLOOR JOISTS		2X6	10'		34	EA
47	STAIR STRINGERS		2X12	14.5'		3	EA
48	STAIR POST		4X4	12		12	LF
49	STAIR		2X6	12'		12	EA
50	STAIR		2X6	6'		18	EA
51	INTERIOR RAILING		2X6	31		31	LF
52	SIMPSON PB44 OR EQ.					3	EA

MATERIAL LIST

C0560B Cabin Plan

Standard W/ Framed Roof Pier Version

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	89.50	16"	36	EA
2	MAIN EXT STUDS		2X6	10'-6"	16"	36	EA
3	MAIN INT PLATES		2X4			138	LF
4	MAIN EXT PLATES		2X6			192	LF
5	MAIN INT STUDS		2X4		16"	36	EA
6	MAIN FLOOR PLYWOOD		3/4"			560	SF
7	UPPER EXT STUDS		2X6	22.00	16"	36	EA
8	UPPER INT PLATES		2x4			34	LF
9	UPPER INT WALL STUDS		2x4	VARIES	16"	26	EA
10	UPPER CEILING S.R. (Optional)		1/2" GYP.			792	SF
11	UPPER EXT WALL S.R. (Optional)		1/2" GYP.			192	SF
12	HEADER, (Main Window)	N/A	4X12	11'		1	EA
13	HEADER, (Ext Main Door)	N/A	4X8	4'		2	EA
14	HEADER, (Main Window)	N/A	4X8	3'		1	EA
15	HEADER, (Main Window)	N/A	4X8	4'		1	EA
16	HEADER, (Main Window)	N/A	4X8	5'		1	EA
17	HEADER, (Upper Window)	B03	4X10	5'		2	EA
18	RAFTERS	B02	2x12	16'	24"	30	EA
19	EAVE BLOCKING		2X	22.5"	24"	28	EA
20	H2.5 RAFTER TIE				24"	30	EA
21	ROOF SHEATH		1/2" CDX			1008	SF
22	ROOF FELT		30# Felt			1008	SF
23	ROOFING					1008	SF
24	BARGE RAFTERS		2X6	16'		6	EA
25	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			720	SF
26	MAIN INT WALL S.R. (Optional)		1/2" GYP.			736	SF
27	MAIN CEILING S.R. (Optional)		1/2" GYP.			560	SF
28	EXT WALL SHEATH		1/2" CDX			720	SF
29	EXT WALL VAPOR		15# Felt			720	SF
30	EXT SIDING (See Plan)		Varies			720	SF
31	CONC. FOOTING, (Footing)		(15) 20" X 20" X 9" DP.			1.16	CY
32	CONC. FOOTING, (Footings)		(15) 8" X 40" DP.			0.65	CY
33	UPPER FLOOR JOISTS	B10	2X8	14'		13	EA
34	UPPER FLOOR JOISTS		2X8	18'		7	EA
35	UPPER FLOOR PLYWOOD		5/8"			240	SF
36	POST		6X6	10'		2	EA
37	BEAM	B05	4X8	10'		3	EA
38	GABLE END STUDS		2X6	260'		260	LF
39	BEAM	B07	4X10	10'		3	EA
40	PORCH JOISTS		2X6	6'		21	EA
41	DECKING		2X6	12'		28	EA
42	PORCH RAFTERS		2X6	10'		21	EA
43	RIDGE BEAM	B01	3-1/8X13-1/2 GLB	14'		2	EA
44	PORCH CEILING JOISTS		2X6	6'		14	EA
45	STRAP		MST28			14	EA

Cont. of C0560B Materials

46	STRAP		MSTC48B3				EA
47	STRAP		LSTA18			14	EA
48	CONCRETE					2.2	CY
49	FLOOR BEAM	B04	4x12	10		4	EA
50	FLOOR BEAM	B09	4x12	7		8	EA
51	FLOOR BEAM	B08	6X12	10		4	EA
52	FLOOR BEAM	B06	4X12	7		4	EA
53	MAIN FLOOR JOISTS		2X6	10'		34	EA
54	STAIR STRINGERS		2X12	14.5'		3	EA
55	STAIR POST		4X4	12		12	LF
56	STAIR		2X6	12'		12	EA
57	STAIR		2X6	6'		18	EA
58	REBAR		#4			270	LF
59	INTERIOR RAILING		2X6	31		31	LF
60	SIMPSON PB44 OR EQ.					3	EA
61	SIMPSON HPAHD22 OR EQ.					15	EA
62	SIMPSON MST28 OR EQ.					14	EA
63	SIMPSON MSTC48B3 OR EQ.					4	EA