

MATERIAL LIST**C0784A Cabin Plan** Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	91.50	16"	79	EA
2	MAIN TREATED SILL		2X6			106	LF
3	MAIN EXT PLATES		2X6			336	LF
4	MAIN INT STUDS		2X4		16"	38	EA
5	MAIN INT PLATES		2X4			147	LF
6	MAIN INT STUDS		2X6		16"	8	EA
7	MAIN INT PLATES		2X6			30	LF
8	HEADER, (Ext Main Door)		4X8	4'		2	EA
9	HEADER, (Main Window)		4X8	5'		3	EA
10	HEADER, (Main Window)		4X8	4'		3	EA
11	RAFTERS	B01	2X10	16' & 18'	16"	44	EA
12	EAVE BLOCKING		2X	14.5	16"	42	EA
13	H2.5 RAFTER TIE				16"	44	EA
14	ROOF SHEATH		1/2 CDX			1464	SF
15	ROOF FELT		30# Felt			1464	SF
16	ROOFING		Composition			1464	SF
17	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			848	SF
18	MAIN INT WALL S.R. (Optional)		1/2" GYP.			784	SF
19	MAIN CEILING S.R. (Optional)		1/2" GYP.			784	SF
20	WALL SHEATH		1/2" CDX			1044	SF
21	WALL VAPOR		15# Felt			1044	SF
22	SIDING (See Plan)					1044	SF
23	CONCRETE					3.02	CY
24	CONCRETE BLOCK		8X8X16			336	EA
25	CEILING JOISTS	B01	2X10	28'	16"	22	EA
26	RIM JOIST					112	LF
27	FLOOR PLYWOOD		5/8" PLY			784	SF
28	RIDGE BEAM		2X12	31'		1	EA
29	FLOOR BEAM		4X10	14'		2	EA
30	FLOOR JOISTS	B03	2X12	13' & 16'		20	EA
31	POSTS (4X4 Posts)			8		4	EA
32	BEAM (Deck Beam)	B07	4X10	10		3	EA
33	BEAM (Porch Beam)	B08	4X10	10		3	EA
34	BARGE RAFTERS		2X6	6', 18', & 20'		2	EA
35	ANCHOR BOLTS		1/2		48"	27	EA
36	HOLD DOWNS		STHD10			2	EA
37	PORCH RAFTERS		2X6	20'		20	EA
38	KNEE WALL PLATES		2X4			84	LF
39	KNEE WALL STUDS		2X4	5'		22	EA